

**Project Information:**

Project Name:  
 Project St. Address:  
 Project City & Zip Code:

**SECTION 08 36 13.3****bp - Storefront Garage & Entry Door Combo Line: (Air, NFRC, U-Factor, SHGC)**

**Use Type:** Sealing the Building Envelope, HVAC Spaces, Energy Code Compliance

**FULL VIEW GLAZED - SECTIONAL OVERHEAD GARAGE & ENTRY DOOR  
 COMBO**

**(IECC & NFRC Certified - US Energy Code Compliant)**

## PART 1 - GENERAL

## 1.01 SUMMARY - Section Includes:

- A. Provide Full View Glazed Aluminum Sectional Overhead Type; Glass Garage & Entry Door Combo (adjacent to each other, separated by a pilaster column), with Insulated Frames, Insulated Glass Units (Tempered): Obscured, Transparent Clear, Tinted, or Insulated Aluminum Panels, as designed per elevation. Frame rails will consist of Extruded Aluminum alloy with either: Clear Anodizing, Powder Coating, Kynar Paint, Simulated Wood Powder Coating, or as specified by Architect (or Project Rep.), for color and type. System will also include all brackets, track system guides, counterbalance, stainless steel hinges, stainless steel rollers, stainless steel fixture hardware, electric motor or manual chain hoist, for a complete finish and operational installation.
1. See 2.02 for Performance Requirements, 2.03 for Components; such as Glazing (type / color), track type, operator type, etc., and 2.04 for finish (type / color).
  2. Provide system to suit field conditions and openings with applicable headroom and side room.

1.02 RELATED REQUIREMENTS (Note: Architect of record to supply additional sections as required.)

- A. Section 06 10 00: Rough Carpentry and Framing. [Adhere to shop drawing min. requirements] General Contractor to provide all structural support, solid blocking, and/or anchoring points.
- B. Section 26 05 00: Basic Materials: Empty conduit from control units to door operator. [By GC]
- C. Section 26 05 00: Electrical service to disconnect near door operator [120-240 single phase dedicated receptacle]

## 1.03 SUBMITTALS – [Administrative Requirements, for submittal procedures]

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

- A. Shop Drawings: Indicate accessories, opening dimensions and required tolerances, connection details, anchorage, spacing, hardware locations, and installation details.
- B. Product Data: Product line information specific to the performance requirements in section 2.02.
- C. Product Certification: Product line information specific to the performance requirements in section 2.02, Current copy of the NFRC Product License; for verification of compliance.
- D. NFRC **C**ertification **A**uthorization **R**eports (NFRC - C.A.R.): Provide a summary of the conforming test procedures and result, which include, but are not limited to: Air Infiltration, Water Resistance, Wind Load, and Structural Testing; in accordance with ASTM E-283, ASTM E-330, ASTM E-331, ASTM E-547.
- E. Samples: Submit two frame finish samples, and two panel samples; illustrating color and finish.
- F. Manufacturer's Installation Instructions: Include any known special procedures required by project conditions; for review by the Architect and Engineer of record.
- G. Operator Manuals [Data Sheet required; if electric operators are specified]: Include specific model #, data for motor and transmission, gearing, lubrication frequency, maintenance, spare part sources, troubleshooting, and adjusting.
- H. Operator Station Control [Data Sheet required; if electric operators are specified]: Include specific model #, type, and information data sheet for motor control. The control station should be located and installed in close proximity to the door, motor operator (left or right side), and provide for direct line to site vision; when operating (opening / closing) the unit.
- I. Optional Aux. Safety Components [Data Sheet; if the electric operators are specified]: Include specific model #, data sheet, maintenance, spare part sources, and manual.
- J. Warranty: Submit manufacturer warranty letter; after installation occurs. Ensure that the warranty forms have been completed in Owner's name, with jobsite address, pictures for verification that the installation occurred correctly, and is registered with manufacturer.
- K. Sustainable Design Submittals: (LEED, National Green Building Standards, Green Globes)
  - 1. Submit documentation from manufacturer of the amounts of pre-consumer and post-consumer recycled content for products specified.
  - 2. Submit documentation showing manufacturing locations and origins of materials for products manufactured and sourced within 500 miles of project location.

## 1.04 QUALITY ASSURANCE

- A. Manufacturer Qualifications: Company specializing in manufacturing of "Full View Type - Glass Garage Doors" specified in this section, with a minimum (70) seventy years or more of documented experience. The Fenestration products must be tested "as a whole system" vs. relying on the data of (1) type of glazing panel alone. The test results must be certified by an independent third-party laboratory, adhere to a quality assurance program; which is re-certified every (4) years, and provide Current NFRC Licensing; with permanent identification plaque, and current CPD #'s (**C**ertified **P**roducts **D**atabase #'s) for verification. See Glazing Panel Type (for specific CPD #) in section 2.03.G

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

- B. Installer Qualifications: If product installation occurs within the State of California, a Factory Direct installation is recommended by **bp** – Glass Garage Doors & Entry Systems, Inc.. Alternatively, a Company specializing in performing the work within this section (which has a min. 20 years of experience), and has acquired a letter of authorization from the Manufacturer; will also be acceptable.
- C. Applicable Codes: Follow all Federal, State, County, and City Building codes as applicable; which include: NEC (National Electric Code) for wiring of motor and motor control requirements as appl., State Energy Code (Specific to Air Infiltration and sealing the Building Envelope); whereas the product specified in this section is tested as a “Whole System” to provide Certified results for: U-Factors, SHGC, VT, Air and Water Infiltration ratings to meet the energy calculations; required per code.
- D. Independent third-party laboratory shall have current NFRC, FL. Miami / Dade licensing.
- E. Products Requiring Electrical Connection: Listed and classified by UL (Underwriters Laboratories Inc.), as suitable for the purpose specified.
- F. Single-Source Supplier: Provide Door(s), tracks, motors, and accessories from one manufacturer; to ensure that manufacturers’ recommendation on various parts have been tested, and properly combined to function as described.

## 1.05 DELIVERY, STORAGE, AND HANDLING

- A. Deliver materials to site in manufacturer’s original, unopened containers and packaging, with labels clearly identifying product name, manufacturer, and model: Ex. “Insulated Frame Line”.
- B. Storage and Handling: Store materials in clean, dry, interior area in accordance with manufacturer’s instructions. Protect materials from damage during handling and installation.

## 1.06 WARRANTY

- A. Provide Closeout Submittals for warranty requirements: Submit manufacturer warranty letter; after installation occurs. Ensure that the warranty forms have been completed in Owner’s name, with jobsite address, pictures for verification that the installation occurred correctly, and is registered with manufacturer.
- B. Manufacturer shall provide high cycle life hardware; as specified on general requirements. Hardware Includes: track hardware, heavy-duty stainless steel hinges, stainless steel sealed roller, high cycle galvanized springs (as avail. by manufacturer), and high tensile aluminum alloy frame rails.

## PART 2 - PRODUCTS

## 2.01 SYSTEM MANUFACTURER

- A. A manufacturer with no less than 70 years of experience in fabricating “Fully Insulated Frame Technology” with ASTM Air & Water Certifications; per NFRC requirements, for “Full View Sectional Overhead - Glass Garage & Entry Doors”
- B. Basis of Design:

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

**bp** - Glass Garage Doors & Entry Systems, Inc.  
 1511 W. 2<sup>nd</sup> St.  
 Pomona, CA 91766  
 Factory Direct / World-Wide Shipping:  
 Toll Free: (877) 442-1716  
 Direct: (626) 442-1716  
 Web: [www.GlassGarageDoors.com](http://www.GlassGarageDoors.com)

**Model Lines:** (Can be combined with any product size)

**bp - Insulated Line:** Seals the Building Envelope (IECC & NFRC Compliant: HVAC Spaces)

**bp - Hurricane Line:** High Wind & Impact, Miami / Dade NOA (FL-HVHZ: Hurricane Zone)

**bp - Classic-Standard Line:** Garages, Warehouses (Non-Insulated / Non-HVAC Spaces)

**bp - Storefront Combo Line:** Entry Door w/ Garage (IECC & NFRC Cert...: HVAC Spaces)

**bp - Entry Door & Gate Line:** Matching Profiles to Garage (Ext. & Weather Exposed Locations)

**Product Size Series:** (Can be combined with any product line)

**bp - 350 Size:** (4ft. - 8ft. wide x 8 ft. high max.) Standard Duty

**bp - 450 HD Size:** (8ft. - 16 ft. wide x 12 ft. high max.) Heavy Duty

**bp - 550 SHD Size:** (16ft. - 24 ft. wide x 16 ft. high max.) Super Heavy Duty

**Product Option:** (Can be combined with any product line)

**Water Resistance Option:** For use in Dry Environments (Per ASTM E331, E547: HVAC Spaces)

- C. Contact **bp** for assistance in verifying: Model Lines, Product Sizes, Options, Glass Type, Operator Type, Width, Height, Weight, and Building Code Requirements.
1. Phone: Toll Free: (877) 442-1716, Direct: (626) 442-1716
  2. Email (Request for Info): [Service@GlassGarageDoors.com](mailto:Service@GlassGarageDoors.com)
  3. Website (Download Info.): [www.GlassGarageDoors.com](http://www.GlassGarageDoors.com)

## 2.02 PERFORMANCE AND CERTIFICATION REQUIREMENTS:

- A. Provide Certification Reports: Product line information must be specific to performance requirements, and must be certified per NFRC and IECC (Energy Code) Requirements for Exterior Doors & Windows. All products must comply with all the applicable requirements of this

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

subsection; which include independent laboratory testing, certified results, and current copy of the NFRC Licensing Agreement; for verification of Compliance.

- B. NFRC [Certified Products Database] (NFRC – C.P.D.): Provide a summary the conforming test procedures and results, which include, but are not limited to: Air Infiltration, Water Resistance, Wind Load, and Structural Testing; in accordance with ASTM E-283, ASTM E-330, ASTM E-331, ASTM E-547, NFRC 100, NFRC 200, NFRC 400
- C. Entire assembly (including frame rails, glass, and panels) shall be certified by the [NFRC \(National Fenestration Rating Council\)](#); Products shall bear “**NFRC Certified labeling**”; which indicates energy performance and technical information. Certifications and Licensing agreements with the NFRC; must be current at the time of manufacturing and/or installation, and shall meet or exceed 2012 – IECC (International Energy Conservation Code – 2016 to current).
- D. Authorized Certifications: No other pseudo certifications will be acceptable, other than the NFRC. Unacceptable pseudo certifications include, but are not limited to: letters from manufacturers, uncertified laboratories, website pages, or other forms of advertising, etc.
1. Fenestration U-Factors & Thermal Transmittance: Per NFRC 100 (Incl. Glazing: U-Factors) which supersedes ANSI/DASMA105
  2. Fenestration SHGC & VT: (Solar Heat Gain Coefficient & Visible Transmittance) Per NFRC 200
  3. Air Infiltration Certification: Per NFRC 400 (See 2.02-C below)
  4. Product must be provided with temporary labels on all glazing and/or panels (for inspection purposes; with certified results) demonstrating compliance to the building inspector, and / or enforcement agency.
  5. Product must be provided with a permanent plaque riveted at the bottom interior (**NFRC Certified labeling**) for inspection by the Architect and/or Representative of record; also demonstrating compliance to the building inspector, and / or enforcement agency.
  6. Fenestration product performance must be certified in accordance with NFRC and requires supporting documentations: Product must be provided with a “**Certificate of Acceptance**” (Found at the end of this section) to be provided for the Architect of Record; during the submittal process. In addition, provide a copy for the Inspection Bureau of record, or the Dept. of Building & Safety; as applicable. This **Fenestration Certificate** will be used as a verifiable source; which traces back to the [www.NFRC.org](http://www.NFRC.org) website; for validating the manufacturer’s compliance.
- C. **Air Infiltration (Certification): Required (per Building Code)**; when measured in accordance with ASTM E-283 and ANSI / DASMA 105: Air Infiltration Test Pressure Differential: 6.24 pounds per square inch. Entire assembly: glass, panels, and Frames shall be certified by an independent Testing Lab; which indicates energy performance, wind load, cyclical testing, and technical information, when measured in accordance with NFRC 100, and NFRC 400 (**As** Licensed on the NFRC.org website, and traces back to the manufacturer; for validating compliance.)
1. **Fully Insulated Frames**: All hollow voids within the frame system, must be filled with a cooperative band to seal all sections, to maintain an airtight seal; for meeting the Building Energy Code Requirements.
- D. **Water Infiltration (Certification)**: System must be tested and certified to mitigate water infiltration, when measured in accordance with ASTM E 331 and ASTM E 547 water testing

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

methods. This package also includes: [(1) each per door] a ½" high x 4"-6" deep x door width; Solid Aluminum Threshold. Designed for heavy traffic [Pedestrian or Vehicular] with ADA compliance. The Water Resistance Package must be combined with the **bp** – Fully Insulated Frame System; which is certified per NFRC 400. (Verify currently Licensed per the [NFRC.org](http://NFRC.org) Website, prior to ordering.) A notarized manufacturers' letter will be provided to the installer, and Architect of record, after the installation is completed. This will verify the installation was completed per the Factory Specification, and testing methods above. A **bp** Factory Rep. must be present during the installation, to verify the proper sealant and installation methods are applied. Note: Safety edges are not compatible with the bp – Water Certified Option, and will be disregarded, if requested in another portion of the specification.

- E. Wind Load: Withstand positive and negative wind loads equal to 25 PSF / 99mph, or as specified by local code; without damage or permanent set, when tested in accordance with ASTM E 330, using 10 second duration of maximum load. (As Licensed on the NFRC.org Website, with Certified Results).
- F. **Test Reports:** Provide an "**NFRC - Certified Report**" summary of the conforming test procedures and results, which include, but are not limited to: Air Infiltration, Water Resistance, Load, and Structural Testing in accordance with ASTM E-283, ASTM E-330, ASTM E-331, ASTM E-547. (As Licensed on the [NFRC.org](http://NFRC.org) Website, per Certified Results).
- G. Torsion Springs: Provide High Cycle Spring Life (20,000–100,000 cycles), as available per Manufacturer engineered calculations; at time of manufacture.
- H. Hinges & Fixtures: 12ga, Stainless Steel, Laser Cut, and Precision Formed, offset numbered type, and graduated to ensure weather tight fit.
- I. Rollers: Stainless Steel Stem, Bushing, and Fitting, with polymer coated races, 500lb-800lb capacity each roller, with precision Stainless Steel Ball Bearings, and mechanically sealed on both sides. [Note: Roller size (2" or 3") must match the appropriate track size]
- J. Additional Components: All components found in section 2.03 are to be provided by the door manufacturer (as a single source supplier) to ensure that manufacturers recommendations on various parts, have been tested, and properly combined to function as described.
- K. Stiles and Rails: Extruded aluminum with tensile strength of at least 38 ksi; (approximately double the strength of 6063-T6 alloy) and complying with ANSI/DASMA 102 / 103.

## 2.03 COMPONENTS

- A. Stile & Rail Alloy: Extruded aluminum with tensile strength of at least 38 ksi; (approximately double the strength of 6063 alloy) and complying with ANSI/DASMA 102 / 103.
- B. Product Sizes: **bp-350** (Top / Btm. rails: 3-1/4" tall x 6' wide door width max.), **bp-450HD** (Top / Btm. rails: 5-3/8" tall x 16' wide door width max.), & **bp-550SHD** (Top / Btm. rails: 7-3/8" tall x 24' door width max.); or as required per the Manufacturer's safety recommendations for the width, height, weight, and track operating clearance.
  - 1. Horizontal Meeting Rails: Combined overall width; 2-3/4" inch.
  - 2. Vertical Intermediate Center Mullions: 1-1/2" inch wide.
  - 3. End Stiles: 3-1/4" inch wide.

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

4. Structural Fastening: Zinc-plated 5/16 inch thru-bolts, nuts, and tension indicating washers to secure stiles and rails.
- C. Door Thickness: 1 3/4" inch, nominal.
- D. Joints: Smooth and tight fitting mitered joints.
- E. Glass Stop Moldings: "Aluminum" snap-in bead type. (No other material types accepted!)
- F. Configuration & Elevation: Product should conform to the general drawings provided, and consistent to the number of panels drawn in width, number of panels drawn in height; or per the safety limits and recommendations of the manufacturer.
- G. Glazing Panel Type: **Note: (Chosen by Architect of Record, or Project Rep.)** [Call Factory for Assistance to designate exact type]
1. Insulated Glass Panels: CBA Certified Products through IGCC; tested in accordance with ASTM E-1290. Tempered glass, FT (Full Tempered); ASTM C-1036 and ASTM C-1048, Condition A, Quality q3, and meeting safety criteria of CPSC 16 CFR 1201, Categories 1-2, and ANSI Z97.1
    - a. Makeup / Color / Type: [1/2" O.A. Thickness]: 1/8" Clear Tempered, Low-E Solarban-60 IG Units; (as per **NFRC CPD# BPC-A-1-00049-00001**) with 1/4" air spacer, and 1/8" clear Tempered; (required by code) – [as default].

1.1 Additional Glass or Panel Choices: Colors, Types, Transparent, Obscured, or other, have been tested and provided for on the CPD (Certified Products Database) of the searchable NFRC Website:  
[http://search.nfrc.org/search/cpd/cpd\\_search\\_detail.aspx?cpdnum=BPC-A-1](http://search.nfrc.org/search/cpd/cpd_search_detail.aspx?cpdnum=BPC-A-1)
- H. Counter Balance: Galvanized torsion springs, head plates, and center spring supports mounted on continuous torsion bar and adjusted to counter weight and travel of door.
1. Cable Drums: Die cast aluminum, paired for track type indicated.
  2. Lift Cables: High tension aircraft cable: 1/8"-1/4" diameter; per Manufacturer requirements
  3. Springs: Galvanized and related hardware as necessary for system indicated.
- I. Track: **Call Factory for Assistance:** (877) 442-1716 to designate Track Type] designated by the provided drawings and field conditions, or chose the appropriate option below. As provided with all track systems: a continuous (floor to ceiling) steel support angles, with a slight taper; to ensure weather-tight fit when in the closed position.
1. Track System Type: **Standard Lift - [as default]**; or in accordance with manufacturer's recommendations based on door weight, height, field conditions at header or as drawn. Standard Track requires 24" min. headroom clearance: from door opening height, to the underside of a ceiling, or fist obstruction: Ex.: Bottom side of a joist, HVAC, Mechanical, Electrical, Plumbing, or other materials that could interfere with the door operation. See shop drawings for more clarity on unobstructed clearances], or in accordance with manufacturer's recommendations based on door weight, height, field conditions at header.
    - a. Other track type options include:
      - i. Standard Track (16" – 24" min. header requirement)
      - ii. High Lift Track (36" – 72" min. header requirement)

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

- iii. Full Vertical Lift Track (Double the door ht. + 18"; from floor to ceiling min.)
  - iv. Low Headroom (Track 2" track: 11" min. or 3" track: 17" min. header req.)
  - v. Roof Pitch Track (12 in 12 pitch or 45 degree max.)
2. Track Size: In accordance with manufacturer's recommendations; based on door weight, width, height, field conditions of header; or as drawn, and per local building code requirements. [Note: Do not exceed 800lbs on 2" track, or 1600lbs on 3" track, based on a formula of 5lbs per square ft.] 2" x 15ga or 3" x 12ga galvanized steel commercial track set, on continuous wall mounted angle support, which extends from the floor up to the door header.
  3. Support Angle: 12ga.- 8ga Galv. steel, or in accordance with manufacturer's recommendations, field conditions of header; or as drawn, and per local building code requirements.
  4. Standard Track Radius: 20 inch, or in accordance with manufacturer's recommendations based on door weight, height, track type and local building code requirements.
- J. Hinges & Fixtures: 12ga, Stainless Steel, Laser Cut, and Precision Formed, offset numbered type, and graduated to ensure weather tight fit.
- K. Rollers: Stainless Steel Stem, Bushing, and Fitting, with polymer coated races, 500lb-800lb capacity each roller, with precision Stainless Steel Ball Bearings, and mechanically sealed on both sides. [Note: Roller size must match the appropriate track type]
- L. Operators: **Choose from (1) of the following:** or **Call Factory for Assistance** to designate exact type and model: (877) 442-1716] as provided by door manufacturer, and in accordance with recommendations based on door weight, height, track type, and local building code requirements.
1. Manual Chain Hoist Type Operator [For Use On High Lift, Full Vert., Standard, or Roof Pitch Track Only!] Note: Low Headroom Tracks will require a Trolley Type Electric Operator for Safety; as provided by door manufacturer, and in accordance with manufacturer's recommendations based on door weight, height, track type and local building code requirements.
  2. Lift Master: Model-MJ (Jackshaft Side Mount) Electric Operator with key station type control – [as default for commercial application]
    - a. Electrical Characteristics: Phase: [Single/Mono], Volts: [110-120], Hertz: 60, Dedicated 20 amp circuit for a (1) Horse Power A/C motor
    - b. Key Switch: If electrified; and/or required for security, or to avoid non authorized personnel to operate.
- M. Operator Station Control [Required if electric operators are specified]: **Push Button Station** or **Key Switch operation** with Constant Contact Pressure, as provided by door manufacturer, and in accordance with manufacturer's recommendations and local building code requirements. The control station should be located and installed in close proximity to the door, motor operator (left or right side), and provide unobstructed line to site vision; when operating (opening / closing) the unit. [Per UL325]
- N. Floor Seal / Btm. Weather Stripping Gasket: Factory applied EPDM gasket full length of bottom section and at each end of top rail making contact with bumper spring.



## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

- O. Side Jamb & Header Weather Stripping: (2) part extruded aluminum and (1) part EPDM system with fasteners concealed inside snap-on cover. (2) sets ea.; mounted at interior perimeter (between jambs and continuous mounted angle, including the header), in addition to the exterior perimeter.
- P. Threshold: 4"-6" wide x ½" high, Solid Aluminum Type. (Designed for heavy traffic [Pedestrian and Vehicular] with ADA compliance.) Tested for use with bp – Insulated Line, Air Infiltration, and Water Resistant Packages.
- Q. Shop Drawings: Indicate accessories, opening dimensions and required tolerances, connection details, anchorage, spacing, hardware locations, and installation details.

## 2.04 FINISH

- A. Color and Coating Type: As selected by Architect, from manufacturer's standard color range..  
**Choose from (1) of the following below [1-4], and delete the items that do not apply:**
  - 1. **Clear Anodized Aluminum:** Clear anodic coating; AA-M12C22A21 3-4 mils thick; ASTM B 244. (10 year color fade warranty; verified by Manufacturer in writing)
  - 2. **Powder Coat:** High Performance Organic Finish: AAMA 2604; multiple coats, thermally cured AAMA 2604 Super Durable Coating. (10 year color fade warranty; verified by Manufacturer in writing)
    - a. Color (Jet Black Anodized): Tiger Drylac Powder Coatings: (38/80020) 10 yr wrty.
  - 3. **Kynar Paint:** Superior Performance Organic Coating System: AAMA 2605; multiple coats, thermally cured polyvinylidene fluoride (PVDF) system. (30 year color fade warranty; verified by Manufacturer in writing)
    - a. Color (Name / Number): ?????? [by Architect, or Project Rep.]
  - 4. **Simulated Wood Grain Powder Coat:** Combination of AAMA 2604 and AAMA 2603 organic coatings. (10 year color fade warranty; verified by Manufacturer in writing)
    - a. Color (Name / Number): ?????? [by Architect, or Project Rep.]
- B. Field Touch-Up Materials: Spray Cans, or as recommended for field application.

## 2.05 MATERIALS

- A. Sheet Steel: Hot-dipped galvanized steel sheet, ASTM A 653 with G40 coating.
- B. Torsion Springs: Galvanized steel; ASTM A 227, Class II zinc coating in accordance with Section 9.2 of ASTM A 641, or Oil Coated per ASTM A 227 - Standard Specification for Steel Wire, Cold-Drawn for Mechanical Springs; 2006. Commercial Projects Include:
- C. Aluminum Sheet (Solid Aluminum Panels; if appl.): ASTM B 209, 5005 alloy, H14 temper, plain surface.
- D. Aluminum Extrusions: At least 38ksi tensile strength; ASTM B 221 and Aluminum Association (AA) standards.

- E. Stainless Steel Hinges & Fixtures: Graduated / Universal Hinges, Intermediate Hinges, Top Fixtures, Bottom Fixtures; and related hardware to be of 12ga. min. thickness, and 304 type min alloy.

## 2.06 REFERENCE STANDARDS

- A. NFRC 100 – National Fenestration Rating Council Incorporated; Procedure for Determining Fenestration Product U-factors; 2010.
- B. NFRC 200 – National Fenestration Rating Council Incorporated; Procedure for Determining Fenestration Product Solar Heat Gain Coefficient and Visible Transmittance at Normal Incidence; 2010.
- C. NFRC 400 – National Fenestration Rating Council Incorporated; Procedure for Determining Fenestration Product Air Leakage; 2010.
- D. AAMA 2603 - Voluntary Specification, Performance Requirements and Test Procedures for Pigmented Organic Coatings on Aluminum Extrusions and Panels; 2002.
- E. AAMA 2604 - Voluntary Specification, Performance Requirements and Test Procedures for High Performance Organic Coatings on Aluminum Extrusions and Panels; 2005.
- F. AAMA 2605 - Voluntary Specification, Performance Requirements and Test Procedures for Superior Performing Organic Coatings on Aluminum Extrusions and Panels; 2005.
- G. ASTM A 227 - Standard Specification for Steel Wire, Cold-Drawn for Mechanical Springs; 2006.
- H. ASTM A 641 - Standard Specification for Zinc-Coated (Galvanized) Carbon Steel Wire; 2009.
- I. ASTM A 653 - Standard Specification for Steel Sheet, Zinc-Coated (Galvanized) or Zinc-Iron Alloy-Coated (Galvannealed) by the Hot-Dip Process; 2009a.
- J. ASTM B 209 - Standard Specification for Aluminum and Aluminum-Alloy Sheet and Plate; 2007.
- K. ASTM B 221 - Standard Specification for Aluminum and Aluminum-Alloy Extruded Bars, Rods, Wire, Profiles, and Tubes; 2008.
- L. ASTM B 244 - Standard Test Method for Measurement of Thickness of Anodic Coatings on Aluminum and of Other Nonconductive Coatings on Nonmagnetic Basis Metals with Eddy-Current Instruments; 2009.
- M. ASTM C 1036 - Standard Specification for Flat Glass; 2006.
- N. ASTM C 1048 - Standard Specification for Heat-Treated Flat Glass—Kind HS, Kind FT Coated and Uncoated Glass; 2004.
- O. ASTM C 1172 - Standard Specification for Laminated Architectural Flat Glass; 2009.
- P. ASTM E 283 - Standard Test Method for Determining Rate of Air Leakage Through Exterior Windows, Curtain Walls, and Doors Under Specified Pressure Differences Across the Specimen; 2004.
- Q. ASTM E 330 - Standard Test Method for Structural Performance of Exterior Windows, Doors, Skylights and Curtain Walls by Uniform Static Air Pressure Difference; 2010.
- R. ASTM E 331 - Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Uniform Static Air Pressure Difference; 2009.

- S. ASTM E 547 - Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls by Cyclic Static Air Pressure Difference; 2009.
- T. ANSI/DASMA 102 - American National Standard Institute/Specifications for Sectional Overhead Type Doors; Door & Access Systems Manufacturers' Association, International; 2004.
- U. ANSI/DASMA 103 – American National Standard Institute/Standard for Counterbalance Systems on Residential Sectional Garage Doors; Door & Access Systems Manufacturers' Association, International; 2006.
- V. ANSI/DASMA 105 – American National Standard Institute/Test Method for Thermal Transmittance and Air Infiltration of Garage Doors; Door & Access Systems Manufacturers' Association, International; 2004.
- W. NFPA 70 - National Electrical Code; National Fire Protection Association; 2008.

### PART 3 - EXECUTION

#### 3.01 VERIFICATION OF SITE CONDITIONS, MEASUREMENTS & REQUIREMENTS; PER SHOP DRAWINGS

- A. Do not begin installation until opening(s) have been properly prepared.
- B. Verify that wall openings are ready to receive work, based on as built dimensions, and tolerances are within specified limits. If not possible, shop drawings must be sign off prior to fabrication.
- C. Verify that electric power is available and of the correct operator characteristics, if applicable.
- D. Verify that field conditions and structural blocking are acceptable, and are ready to receive this work.
- E. Verify that related items; whether provided under other sections or not (millwork, fixtures, shelves, cabinets, moldings, trim work, floor transitions to door frame, etc.), are properly located, and will not interfere with the door operation.
- F. Verify that built-in items (Electrical, Mechanical: Plumbing, HVAC Ducting & Registers, Fire Sprinklers, are in proper location, will not interfere with the proper operation of the door, operator, track, etc., and ready for installation of this work.
- G. Prime Contractor to verify required clearances and solid blocking requirements for door operation, including but not limited to; all existing equipment, structural, mechanical, or electrical components; near or around garage door DO NOT CONFLICT WITH OVERHEAD ROLLING DOOR, ASSOCIATED TRACK, SOLID BLOCKING, OR OPERATOR prior to fabrication or installation of new door units. Verify that the Head-Plate / Bearing Brackets are bolted directly to the structural header, and not sitting on the horizontal track. Negligence in doing so can result in death, injury, or damage.

#### 3.02 PREPARATION

- A. Prepare opening to permit correct installation of door to perimeter air and vapor barrier seal.

## Full View Glazed Sectional Overhead &amp; Entry Door Combo: (bp - Storefront Line)

- B. Prime Contractor to verify required clearances and solid blocking requirements for door operation, including but not limited to; all existing equipment, structural, mechanical, or electrical components; near or around garage door. DO NOT CONFLICT WITH OVERHEAD ROLLING DOOR, ASSOCIATED TRACK, SOLID BLOCKING, OR OPERATOR prior to fabrication or installation of new door units. Verify that the Head-Plate / Bearing Brackets are bolted directly to the structural header, and not sitting on the horizontal track. Negligence in doing so can result in death, injury, or damage.

## 3.03 INSTALLATION

- A. Install door unit assembly in accordance with manufacturer's instructions.
- B. Anchor assembly to wall construction and building framing without distortion or stress.
- C. Securely brace door tracks suspended from structure. Secure tracks to structural members only.
- D. Fit and align door assembly including hardware.
- E. Coordinate installation of electrical service. Complete power and control wiring from disconnect to unit components.
- F. Coordinate installation of sealants and backing materials at frame perimeter as specified in Section 07 9005.
- G. Provide the necessary equipment for a safe installation, which include, but are not limited to; scissor lifts [doors over 8ft high], cranes, specialty hoisting, harness, or rigging equipment.
- H. Provide the necessary transporting of freight, shipping crates, boxes, and sundries to ensure the product is not damaged during shipping, transporting to the site of installation, or installation.
- I. Prime Contractor to verify required clearances and solid blocking requirements for door operation, including but not limited to; all existing equipment, structural, mechanical, or electrical components; near or around garage door. DO NOT CONFLICT WITH OVERHEAD ROLLING DOOR, ASSOCIATED TRACK, SOLID BLOCKING, OR OPERATOR prior to fabrication or installation of new door units. Verify that the Head-Plate / Bearing Brackets are bolted directly to the structural header, and not sitting on the horizontal track. Negligence in doing so can result in death, injury, or damage.

## 3.04 TOLERANCES

- A. Maximum Variation from Plumb: 1/16 inch.
- B. Maximum Variation from Level: 1/16 inch.
- C. Maximum Deflection [Width or Height: 0.75%, when in the open or closed position.
- D. Maintain dimensional tolerances and alignment with adjacent work.
- E. Operating Weight: Door weights are approx. 5lbs. pr. sq. ft. max. (Based on 1/2" O.A. Insulated Glass Units: 1/8" Tempered; with 1/4" air spacer, and 1/8" Tempered – [as default].

### 3.05 ADJUSTING

- A. Adjust door assembly for smooth operation and full contact with weather stripping.
- B. Have manufacturer's field representative present to confirm proper operation and identify adjustments to door assembly for specified operation.

### 3.06 CLEANING

- A. Remove temporary labels and visible markings.
- B. Clean doors, frame rails, and glazing, with soapy water, and dry with a soft rag to avoid scratches.

### 3.07 PROTECTION

- A. Protect installed products from damage during subsequent construction.
- B. Do not permit construction traffic through overhead door openings after adjustment and cleaning.

### 3.08 FENSTRATION ACCEPTANCE CERTIFICATE

- A. Provide the "Certificate of Acceptance Form - **NRCA-ENV-02-A**" below; to the Architect of Record, and the local City Municipality, Building Dept., and/or Jobsite Inspector, to ensure the product will Pass Final Inspection.

<b>CERTIFICATE OF ACCEPTANCE</b>		<b>NRCA-ENV-02-A</b>
<b>Fenestration Acceptance Certificate</b>		<b>(Page 1 of 2)</b>
Project Name/Address:		
System Name or Identification/Tag: <b>"BP – Glass Garage Doors &amp; Entry Systems, Inc."</b>	System Location or Area Served: <b>USA, Canada, European Union:</b>	

Climate Zone: ( ) <b>"BP – Glass Garage Doors are certified for Zones 1-7"</b>	Enforcement Agency Use: Checked by/Date
--	---

*Note: The Enforcement Agency may optionally verify any Fenestration being installed for authenticity by accessing <http://cmast.nfrc.org/Project/CertificateFind.aspx> for NFRC CMAST Certificate Labels or NFRC Certificate Labels <http://search.nfrc.org/search/searchDefault.aspx>. See Reference Nonresidential Appendix NA7 for additional information.*

<b>BUILDING INFORMATION</b>						
BUILDING TYPE:	<input type="checkbox"/> Low-rise Nonresidential	<input type="checkbox"/> Low-rise Schools	<input type="checkbox"/> High Rise Residential	<input type="checkbox"/> Hotel/Motel Guest Room		
PHASE OF CONSTRUCTION:	<input type="checkbox"/> New Building Construction		<input type="checkbox"/> Addition	<input type="checkbox"/> Alteration		
TYPE OF LABEL CERTIFICATE:	<input checked="" type="checkbox"/> <b>Rated NFRC Component Modeling Approach</b>		<input type="checkbox"/> FC-1 for Nonrated	<input type="checkbox"/> FC-1 for Nonrated		
	(CMA) Label Certificate or <b>NFRC</b> Certified Label		Fenestration Values < 1,000 ft <sup>2</sup>	Fenestration Values ≥ 1,000 ft <sup>2</sup>		
TYPE OF INSTALLED FENESTRATION:	<input checked="" type="checkbox"/> <b>Vertical Fenestration</b>	<input type="checkbox"/> Tubular Daylighting Device (TDD)	<input type="checkbox"/> Skylight	<input type="checkbox"/> Dynamic Glazing	<input type="checkbox"/> Window Film	<input type="checkbox"/> Block Glass

**STATEMENT OF ACCEPTANCE**  
*This Certificate of Acceptance summarizes the results of the Acceptance test as specified in the Reference Nonresidential Appendix, NA7.4. Additional related references are in Sections §10-103(a)4, §10-111, §116(a)5 of the Energy Efficiency Standards.*

**SUMMARY OF FENESTRATION VERIFICATION AND INSPECTION BY RESPONSIBLE PARTY**  
*Individuals who perform the field testing and verification work, and provide the information required for completion of the Certificate of Acceptance documentation are not required to be licensed professionals. However, the person who signs the Certificate of Acceptance document to certify compliance with the acceptance requirements shall be licensed as specified in Standards Section 10-103(a)4 and NA7.3.1.*

*The Responsible Person or Party shall verify the thermal performance (U-factor, SHGC and VT) of each specified fenestration product being installed matches the fenestration the NFRC Label Certificate, the CEC energy compliance documentation and building plans. Note: A maximum of 4 NFRC Product Listings for each Certificate of Acceptance.*

**For NFRC Rated Product (If more than 8 fenestration products use additional sheets)**

<i>If Product is rated by NFRC then enter the ID # in each column. This includes any of the types of installed fenestration listed above.</i>	1	2	3	4
	NFRC Label Certificate ID # <b>BPC-A-1-00049-00001</b>	NFRC Label Certificate ID #	NFRC Label Certificate ID #	NFRC Label Certificate ID #
	5	6	7	8
	NFRC Label Certificate ID#	NFRC Label Certificate ID #	NFRC Label Certificate ID #	NFRC Label Certificate ID #

**For All Fenestration: Verify and Cross Reference:**

<i>If receipts or orders are available and it identifies the NFRC ID# then cross reference against the NFRC Label Certificate to match ID#s; or</i>	1	2	3	4
	<input type="checkbox"/> Delivery Receipt(s) <input type="checkbox"/> Purchase Order or <input type="checkbox"/> Detailed Receipt	<input type="checkbox"/> Delivery Receipt(s) <input type="checkbox"/> Purchase Order or <input type="checkbox"/> Detailed Receipt	<input type="checkbox"/> Delivery Receipt(s) <input type="checkbox"/> Purchase Order or <input type="checkbox"/> Detailed Receipt	<input type="checkbox"/> Delivery Receipt(s) <input type="checkbox"/> Purchase Order or <input type="checkbox"/> Detailed Receipt
<i>Cross reference the efficiencies listed on the NFRC Label Certificate of FC-1 matches the building plans window schedule of efficiencies.</i>	<input type="checkbox"/> Cross Reference and Matches Building Plans	<input type="checkbox"/> Cross Reference and Matches Building Plans	<input type="checkbox"/> Cross Reference and Matches Building Plans	<input type="checkbox"/> Cross Reference and Matches Building Plans

<b>CERTIFICATE OF ACCEPTANCE</b>		<b>NRCA-ENV-02-A</b>
<b>Fenestration Acceptance Certificate</b>		<b>(Page 2 of 2)</b>
Project Name/Address:		
System Name or Identification/Tag: <b>"BP – Glass Garage Doors &amp; Entry Systems, Inc."</b>	System Location or Area Served: <b>USA, Canada, European Union:</b>	

**FIELD TECHNICIAN'S DECLARATION STATEMENT**

- I certify under penalty of perjury, under the laws of the State of \_\_\_\_\_, the information provided on this form is true and correct.
- I am the person who performed the acceptance requirements verification reported on this Certificate of Acceptance (Field Technician).
- I certify that the construction/installation identified on this form complies with the acceptance requirements indicated in the plans and specifications approved by the enforcement agency, and conforms to the applicable acceptance requirements and procedures specified in Reference Nonresidential Appendix NA7.
- I have confirmed that the Installation Certificate(s) for the construction/installation identified on this form has been completed and is posted or made available with the building permit(s) issued for the building.

Company Name:		
Field Technician's Name:	Field Technician's Signature:	
	Date Signed:	Position With Company (Title):

**RESPONSIBLE PERSON'S DECLARATION STATEMENT**

- I certify under penalty of perjury, under the laws of the State of \_\_\_\_\_, that I am the Field Technician, or the Field Technician is acting on my behalf as my employee or my agent and I have reviewed the information provided on this form.
- I am a licensed contractor, architect, or engineer, who is eligible under Division 3 of the Business and Professions Code, in the applicable classification, to take responsibility for the scope of work specified on this document and attest to the declarations in this statement (responsible person).
- I certify that the information provided on this form substantiates that the construction/installation identified on this form complies with the acceptance requirements indicated in the plans and specifications approved by the enforcement agency, and conforms to the applicable acceptance requirements and procedures specified in Reference Nonresidential Appendix NA7.
- I have confirmed that the Installation Certificate(s) for the construction/installation identified on this form has been completed and is posted or made available with the building permit(s) issued for the building.
- I will ensure that a completed, signed copy of this Certificate of Acceptance shall be posted, or made available with the building permit(s) issued for the building, and made available to the enforcement agency for all applicable inspections. I understand that a signed copy of this Certificate of Acceptance is required to be included with the documentation the builder provides to the building owner at occupancy.

Company Name:		Phone:
Responsible Person's Name:	Responsible Person's Signature:	
License:	Date Signed:	Position With Company (Title):

**Documentation Author's Declaration Statement**

- I certify that this Certificate of Acceptance documentation is accurate and complete.**

Name:	Signature:
Company :	Date:
Address:	If Applicable CEA or CEPE (Certification #):
City/State/Zip:	Phone:

08 36 13.3

Full View Glazed Sectional Overhead & Entry Door Combo: (bp - Storefront Line)

[END OF SECTION 08 36 13.20]



# bp Glass Garage Doors & Entry Systems, Inc.

## Insulated Line (US & Intl. Pat.)

bp Glass Garage Doors **“Fully Insulated Frame Technology”** (US & Intl. Pat.) is the key component for eliminating air leakage, when using Full Vision Type Doors to “seal the building envelope, or any HVAC climate controlled space.” Our Insulated Frame System, also enhances acoustical performance: STC = 36±  
What is the point in having Insulated Glass Panels, if the frame leaks Air or Water?

bp **Insulated Line** glazing options consists of: 1/2” Krypton or Argon filled IG units. Each glass panel is sealed during fabrication process, to ensure an air-tight fit. Glazing options are available in transparent, obscured, low-E glass, and in a variety of color tints, to suit your design. Every glass type has a unique set of energy ratings: **U-Values: ±/ - 0.22 - 0.99, SHGC: ±/ - 0.15 - 0.45, and VT: 0.02 - 0.46;** and is ultimately determined by the glass specified on your project.

→ (Keep in mind that IG units (Insulated Glass) are ineffective if the frame leaks air!)

The bp - **NFRC Air Resistance Package** provides an airtight seal; where building code compliance is required. bp doors have been certified as a “whole system”, and not just glass alone. Testing reports and CPD #'s (Certified Products Database) for various glass types can be found at the **National Fenestration Rating Council: [www.NFRC.org](http://www.NFRC.org)**



Note: The **“bp - Water Resistant Option”**, Per ASTM E331 & E547 [SOLD SEPARATELY], must be combined with the **“bp - Air Infiltration Option”** to function as tested. This **CAN NOT BE INSTALLED AFTERWARDS!**

Note: **Doors or Windows WITHOUT Certified “NFRC” labels, are simply FALSE ADVERTISING, and ILLEGAL per the “IECC ENERGY CODE”.** Insulated Glass alone WILL NOT make a Door or Window Insulated, unless it has been certified by the [NFRC.org](http://NFRC.org)

**24ft. wide x 18ft. high (max.)**



bp - Air Leakage Resistance Package*	
Air Leakage Resistance Results ( Per NFRC 400 / ASTM E283 / DASMA 105)	
Residential Standard	0.3 CFM
Commercial Standard	0.4 CFM
<b>bp - Glass Garage Doors results</b>	<b>0.06 CFM</b>

\*Note: The lower the CFM = Better Air Leakage Resistance. Thermal ratings for U-factor, SHGC, VT available upon request, per NFRC 100 / 200.



# **bp** Glass Garage Doors & Entry Systems, Inc.

## Storefront Garage Combo Line (US & Intl. Pat.)

**bp** manufactures Glass Garage & Matching Entry Doors (in combination), to comprise our **bp Storefront Garage Combo Line**. This Architectural blend, focuses on Form and Function, allowing the end user to implement an operable window wall, or limit access to just an entry door... All while sealing the bldg. envelope.

The **bp NFRC Air Resistance Package** provides an airtight seal; where building energy code compliance is required. **bp** Glass Doors have been tested and certified as a “whole system”, and not just glass alone. The **bp “Fully Insulated Frame Technology” (US & Intl. Pat.)** is the key component for eliminating air leakage, when using Full Vision Type Doors to seal the building envelope, or any HVAC climate-controlled space... Our products far exceed the allowable resi. & com. standards.



**FACTORY DIRECT – WORLDWIDE SHIPPING** - 1511 W 2<sup>nd</sup> St. Pomona, CA 91766 – TF: (877) 422-1716 - Fax (626) 579-5320 - Web: [www.glassgaragedoors.com](http://www.glassgaragedoors.com)

# bp Glass Garage Doors & Entry Systems, Inc.

## bp - Water Resistance Option



**24ft. wide x 18ft. high (max.)**

Note: The **bp** - Water Resistant Option must be combined with the **bp** - Air Resistant Package, to function as tested!  
**CAN NOT BE INSTALLED AFTERWARDS.**

The **bp** - Water Resistance Option has been Certified for: Residential, Lite Commercial, and Commercial performance.

The following testing methods were utilized:

- ❖ ASTM E331- Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors, and Curtain Walls, by **Uniform** Static Air Pressure Differentials.
- ❖ ASTM E547 – Standard Test Method for Water Penetration of Exterior Windows, Skylights, Doors and Curtain Walls, by **Cyclical** Static Air Pressure Differentials.

Test Method E331 and E547			Title of Test Water Resistance			Results No Leakage	
Classification			DP	Pa	PSF	mph	" H2O
Res.	Lite Com.	Com.	30	220	4.59	42	0.88"

